

Related U.S. Application Data

Dec. 5, 2019, now Pat. No. 11,215,776, which is a continuation of application No. 15/985,068, filed on May 21, 2018, now Pat. No. 10,502,912, which is a continuation of application No. 15/373,709, filed on Dec. 9, 2016, now Pat. No. 9,977,208, which is a continuation of application No. 14/331,873, filed on Jul. 15, 2014, now Pat. No. 9,557,505, which is a continuation-in-part of application No. PCT/US2014/030969, filed on Mar. 18, 2014.

- (60) Provisional application No. 61/846,392, filed on Jul. 15, 2013, provisional application No. 61/802,989, filed on Mar. 18, 2013.

(51) Int. Cl.

G02B 6/38 (2006.01)
H01B 11/22 (2006.01)

(56) References Cited

U.S. PATENT DOCUMENTS

4,220,812 A	9/1980	Ney et al.	6,463,198 B1	10/2002	Coleman
4,359,598 A	11/1982	Dey et al.	6,493,491 B1	12/2002	Shen et al.
4,365,865 A	12/1982	Stiles	6,501,888 B2	12/2002	Gimblet et al.
4,401,361 A	8/1983	Slaughter	6,542,674 B1	4/2003	Gimblet
4,420,220 A	12/1983	Dean et al.	6,563,990 B1	5/2003	Hurley et al.
4,467,138 A	8/1984	Brorein	6,567,592 B1	5/2003	Gimblet et al.
4,497,537 A	2/1985	Dench	6,599,025 B1	7/2003	Deutsch
4,552,432 A	11/1985	Anderson et al.	6,621,964 B2	9/2003	Quinn et al.
4,595,839 A	6/1986	Braun et al.	6,687,437 B1	2/2004	Starnes et al.
4,695,127 A	9/1987	Ohlhaber et al.	6,714,710 B2	3/2004	Gimblet
4,723,832 A	2/1988	Okazato et al.	6,719,461 B2	4/2004	Cull
4,729,628 A	3/1988	Kraft et al.	6,738,547 B2	5/2004	Spooner
4,761,053 A	8/1988	Cogelia et al.	6,744,954 B1	6/2004	Tanaka et al.
4,787,705 A	11/1988	Shinmoto et al.	6,755,575 B2	6/2004	Kronlund et al.
4,844,575 A	7/1989	Kinard et al.	6,758,693 B2	7/2004	Inagaki et al.
4,852,965 A	8/1989	Mullin et al.	6,792,184 B2	9/2004	Conrad et al.
4,867,527 A	9/1989	Dotti et al.	6,836,603 B1	12/2004	Bocanegra et al.
4,895,426 A	1/1990	Pinson	6,845,200 B1	1/2005	Quinn
5,109,457 A	4/1992	Panuska et al.	6,847,767 B2	1/2005	Hurley et al.
5,138,685 A	8/1992	Arroyo et al.	6,931,183 B2	8/2005	Panak et al.
5,155,304 A	10/1992	Gossett et al.	6,965,718 B2	11/2005	Koertel
5,268,971 A	12/1993	Nilsson et al.	7,006,740 B1	2/2006	Parris
5,369,518 A	11/1994	Aslami et al.	7,085,459 B2	8/2006	Conrad et al.
5,448,670 A	9/1995	Blew et al.	7,158,703 B2	1/2007	Mjelstad
5,469,523 A	11/1995	Blew et al.	7,184,634 B2	2/2007	Hurley et al.
5,494,461 A	2/1996	Bippus et al.	7,218,821 B2	5/2007	Bocanegra et al.
5,539,851 A	7/1996	Taylor et al.	7,225,534 B2	6/2007	Kachmar
5,555,336 A	9/1996	Winslow	7,272,281 B2	9/2007	Stahulak et al.
5,555,338 A	9/1996	Haag et al.	7,310,430 B1	12/2007	Mallya et al.
5,557,698 A	9/1996	Gareis et al.	7,362,936 B2	4/2008	Stark et al.
5,636,308 A	6/1997	Personne et al.	7,371,014 B2	5/2008	Willis et al.
5,651,081 A	7/1997	Blew et al.	7,387,517 B2	6/2008	Kusuda et al.
5,677,974 A	10/1997	Elms et al.	7,401,985 B2	7/2008	Aronson et al.
5,737,470 A	4/1998	Nagano et al.	7,445,389 B2	11/2008	Aronson
5,745,627 A	4/1998	Arroyo et al.	7,454,107 B2	11/2008	Miller et al.
5,778,116 A	7/1998	Tomich	7,467,896 B2	12/2008	Melton et al.
5,778,652 A	7/1998	Kunze	7,494,287 B2	2/2009	Wang et al.
5,838,858 A	11/1998	White	7,499,616 B2	3/2009	Aronson et al.
5,896,480 A	4/1999	Scharf et al.	7,532,796 B2	5/2009	Chiasson
5,913,003 A	6/1999	Arroyo et al.	7,539,380 B1	5/2009	Abernathy et al.
5,982,966 A	11/1999	Bonice	7,567,741 B2	7/2009	Abernathy et al.
6,088,499 A	7/2000	Newton et al.	7,643,631 B2	1/2010	Kennedy
6,101,305 A	8/2000	Wagman et al.	7,643,713 B2	1/2010	Büthe et al.
6,110,213 A	8/2000	Vinciarelli et al.	7,692,098 B2	4/2010	Wyatt, II et al.
6,142,802 A	11/2000	Berg et al.	7,693,375 B2	4/2010	Freeland et al.
6,169,834 B1	1/2001	Keller	7,712,976 B2	5/2010	Aronson et al.
6,195,487 B1	2/2001	Anderson et al.	7,744,288 B2	6/2010	Lu et al.
6,236,789 B1	5/2001	Fitz	7,762,727 B2	7/2010	Aronson
6,343,172 B1	1/2002	Schiestle	7,778,510 B2	8/2010	Aronson et al.
6,347,172 B1	2/2002	Keller et al.	7,796,853 B2	9/2010	Abernathy et al.
6,363,192 B1	3/2002	Spooner	7,837,397 B2	11/2010	Fingler et al.
6,370,303 B1	4/2002	Fitz et al.	7,876,989 B2	1/2011	Aronson et al.
			7,897,873 B2	3/2011	Gemme et al.
			7,918,609 B2	4/2011	Melton et al.
			8,041,166 B2	10/2011	Kachmar
			8,059,929 B2	11/2011	Cody et al.
			8,083,417 B2	12/2011	Aronson et al.
			8,155,525 B2	4/2012	Cox
			8,175,433 B2	5/2012	Caldwell et al.
			8,184,935 B2	5/2012	Kachmar
			8,204,348 B2	6/2012	Keller et al.
			8,224,141 B2	7/2012	Kachmar et al.
			8,238,706 B2	8/2012	Kachmar
			8,244,087 B2	8/2012	Sales Casals et al.
			8,249,410 B2	8/2012	Andrus et al.
			8,270,838 B2	9/2012	Cox
			8,290,320 B2	10/2012	Kachmar
			8,297,854 B2	10/2012	Bickham et al.
			8,301,003 B2	10/2012	de los Santos Campos et al.
			8,328,433 B2	12/2012	Furuyama
			8,358,893 B1	1/2013	Sanderson et al.
			8,363,994 B2	1/2013	Kachmar
			8,376,630 B2	2/2013	Wang et al.
			8,480,312 B2	7/2013	Smith et al.
			8,538,216 B2	9/2013	Abernathy et al.
			8,682,124 B2	3/2014	Logan
			8,712,200 B1	4/2014	Abernathy et al.
			8,761,564 B2	6/2014	Su et al.
			9,274,302 B2	3/2016	Gimblet et al.

(56)

References Cited**U.S. PATENT DOCUMENTS**

9,472,314 B2 10/2016 Kachmar et al.
 9,557,505 B2 1/2017 Huegerich et al.
 9,837,186 B2 12/2017 Kachmar et al.
 9,893,811 B2 2/2018 Chappell et al.
 9,977,208 B2 5/2018 Huegerich et al.
 10,014,958 B2 7/2018 Sipes, Jr. et al.
 10,171,180 B2 1/2019 Sipes, Jr. et al.
 10,247,893 B1 4/2019 Elkayam et al.
 10,277,329 B2 4/2019 Sipes, Jr. et al.
 10,277,330 B2 4/2019 Sipes, Jr.
 10,502,912 B2 12/2019 Huegerich et al.
 10,855,381 B2 12/2020 Sipes, Jr.
 11,025,345 B2 6/2021 Sipes, Jr. et al.
 11,215,776 B2 1/2022 Huegerich et al.
 11,656,418 B2 5/2023 Huegerich et al.
 2002/0015565 A1 2/2002 Imamura
 2002/0126967 A1 9/2002 Panak et al.
 2002/0136510 A1 9/2002 Heinz et al.
 2002/0147978 A1 10/2002 Dolgonos et al.
 2003/0108351 A1 6/2003 Feinberg et al.
 2003/0202756 A1 10/2003 Hurley et al.
 2003/0215197 A1 11/2003 Simon et al.
 2004/0258165 A1 12/2004 Peltonen
 2005/0002622 A1 1/2005 Sutehall et al.
 2005/0185903 A1 8/2005 Koertel
 2006/0045443 A1 3/2006 Blazer
 2006/0153516 A1 7/2006 Napiorkowski et al.
 2006/0165355 A1 7/2006 Greenwood et al.
 2006/0239183 A1 10/2006 Robitaille et al.
 2006/0246772 A1 11/2006 Yamaguchi et al.
 2006/0291787 A1 12/2006 Seddon
 2007/0248358 A1 10/2007 Sauer
 2007/0269170 A1 11/2007 Easton et al.
 2008/0037941 A1 2/2008 Malliya et al.
 2008/0131132 A1 6/2008 Solheid et al.
 2008/0219621 A1 9/2008 Aldeghe et al.
 2008/0260389 A1 10/2008 Zheng
 2008/0290729 A1 11/2008 Schoenberg et al.
 2008/0310848 A1 12/2008 Yasuda et al.
 2009/0003792 A1 1/2009 Thompson
 2009/0041413 A1 2/2009 Hurley
 2009/0097855 A1 4/2009 Thelen et al.
 2009/0297104 A1 12/2009 Kachmar
 2010/0007220 A1 1/2010 Lo
 2010/0080563 A1 4/2010 DiFonzo et al.
 2010/0150556 A1 6/2010 Soto et al.
 2010/0200270 A1 8/2010 Gemme et al.
 2010/0209058 A1 8/2010 Ott
 2010/0290787 A1 11/2010 Cox
 2010/0321591 A1 12/2010 Onomatsu
 2011/0021069 A1 1/2011 Hu et al.
 2011/0038582 A1 2/2011 DiFonzo et al.
 2011/0091174 A1 4/2011 Kachmar
 2011/0150401 A1 6/2011 Furuyama
 2011/0188815 A1 8/2011 Blackwell, Jr. et al.
 2011/0217010 A1 9/2011 Kachmar
 2011/0268446 A1 11/2011 Cune et al.
 2011/0268452 A1 11/2011 Beamon et al.
 2011/0280527 A1 11/2011 Tamura
 2011/0293227 A1 12/2011 Wu
 2011/0311191 A1 12/2011 Hayashishita et al.
 2012/0008904 A1 1/2012 Han et al.
 2012/0008905 A1 1/2012 Han et al.
 2012/0008906 A1 1/2012 Han et al.
 2012/0057821 A1 3/2012 Aronson et al.
 2012/0080225 A1 4/2012 Kim et al.
 2012/0114288 A1 5/2012 Wu
 2012/0141064 A1 6/2012 Walker
 2012/0191997 A1 7/2012 Miller
 2012/0230637 A1 9/2012 Kachmar
 2012/0242168 A1 9/2012 Tsai et al.
 2012/0281952 A1 11/2012 McCulloch
 2012/0281953 A1 11/2012 Choi et al.
 2012/0288245 A1 11/2012 Hurley et al.
 2012/0295486 A1 11/2012 Petersen et al.

2012/0315004 A1 12/2012 Register, III et al.
 2013/0011106 A1 1/2013 Congdon, II et al.
 2013/0022318 A1 1/2013 Fingler et al.
 2013/0058613 A1 3/2013 Jost et al.
 2013/0094821 A1 4/2013 Logan
 2013/0094823 A1 4/2013 Gimblet et al.
 2013/0173939 A1 7/2013 Peto
 2013/0287349 A1 10/2013 Faulkner et al.
 2013/0330086 A1 12/2013 Berlin et al.
 2014/0016527 A1 1/2014 Coffey
 2014/0072264 A1 3/2014 Schroder et al.
 2014/0087742 A1 3/2014 Brower et al.
 2014/0258742 A1 9/2014 Chien et al.
 2014/0314412 A1 10/2014 Soto et al.
 2014/0338968 A1 11/2014 Kachmar
 2015/0078740 A1 3/2015 Sipes, Jr. et al.
 2015/0125146 A1 5/2015 Erreygers et al.
 2015/0304742 A1 10/2015 Siddhaye et al.
 2015/0309271 A1 10/2015 Huegerich et al.
 2015/0378118 A1 12/2015 Huegerich et al.
 2016/0020911 A1 1/2016 Sipes, Jr. et al.
 2016/0050029 A1 2/2016 Huegerich et al.
 2016/0294475 A1 10/2016 Chappell et al.
 2016/0300643 A1 10/2016 Kachmar et al.
 2017/0184799 A1 6/2017 Huegerich et al.
 2018/0061529 A1 3/2018 Kachmar et al.

FOREIGN PATENT DOCUMENTS

AU 2010235866 A1 11/2010
 CN 101449189 A 6/2009
 CN 201359882 Y 12/2009
 CN 101925841 A 12/2010
 CN 201868149 U 6/2011
 CN 102136649 A 7/2011
 CN 102263340 A 11/2011
 CN 102934377 A 2/2013
 CN 103428056 A 12/2013
 EP 0 629 889 A1 12/1994
 EP 1 650 888 A1 4/2006
 EP 2 393 220 A1 12/2011
 EP 2 393 222 A1 12/2011
 EP 2 676 161 A0 12/2013
 GB 2468274 B 7/2013
 JP 10-145299 A 5/1998
 KR 10-1997-0060748 A 8/1997
 KR 1999-0040389 A 6/1999
 KR 20-0273482 Y1 4/2002
 WO 2010/102201 A2 9/2010
 WO 2011/146720 A2 11/2011
 WO 2012/058181 A1 5/2012
 WO 2012/112532 A2 8/2012
 WO 2013/117598 A2 8/2013

OTHER PUBLICATIONS

European Search Report for Application No. 14797917.3 mailed Dec. 6, 2016.
 Extended European Search Report for Application No. 14825675.3 mailed Jan. 30, 2017.
 Extended European Search Report for Application No. 14751600.9 mailed Mar. 22, 2017.
 Extended European Search Report for Application No. 21168354.5 mailed Aug. 23, 2021.
 “GE—Critical Power, DAS and Small Cell Powering Architectures,” DAS and Small Cell Congress, May 1, 2013; 22 pages.
 IEC 60603-7-7, Second Edition Jun. 2006, “Connectors for electronic equipment”, Part 7-7.
 International Search Report and Written Opinion for PCT/US2014/015969 mailed Jul. 21, 2014.
 International Search Report and Written Opinion for PCT/US2014/000115 mailed Sep. 24, 2014.
 International Search Report and Written Opinion for PCT/US2014/046678 mailed Nov. 6, 2014.
 International Search Report and Written Opinion for PCT/US2014/030969 mailed Nov. 26, 2014.

(56)

References Cited

OTHER PUBLICATIONS

Littelfuse Inc., “Transient Suppression Devices and Principles” application note AN9768, dated Jan. 1998. Retrieved from http://www.littelfuse.com/~media/electronics_technical/application_notes/varistors/littelfuse_transient_suppression_devices_and_principles_application_note.pdf.

OneReach PoE Extender System brochure from Berk-Tek, 8 pages (Jan. 2011).

Silvertel, “Ag5700 200W Powered Device Module” datasheet, dated Aug. 2012. Retrieved from <http://www.silvertel.com/images/datasheets/Ag5700-datasheet-200W-Power-over-Ethernet-PoE-PD.pdf>.

European Examination Report for EP Application No. 21168354.5 mailed Oct. 17, 2024.




FIG. 1




FIG. 2




FIG. 3




FIG. 4




FIG. 5






FIG. 6






FIG. 9




FIG. 10




FIG. 11




FIG. 12




FIG. 13




FIG. 14




FIG. 15




FIG. 16

POWER AND OPTICAL FIBER INTERFACE**CROSS-REFERENCE TO RELATED APPLICATIONS**

This application is a continuation application of U.S. Non-Provisional patent application Ser. No. 18/200,154, filed May 22, 2023, which is a continuation application of U.S. patent application Ser. No. 17/567,331, filed Jan. 3, 2022, now U.S. Pat. No. 11,656,418, issued May 23, 2023, which is a continuation application of U.S. patent application Ser. No. 16/704,964, filed Dec. 5, 2019, now U.S. Pat. No. 11,215,776, issued Jan. 2, 2022, which is a continuation application of U.S. Non-Provisional patent application Ser. No. 15/985,068, filed May 21, 2018, now U.S. Pat. No. 10,502,912, issued Dec. 10, 2019, which is a continuation of U.S. Non-Provisional patent application Ser. No. 15/373,709, filed Dec. 9, 2016, now U.S. Pat. No. 9,977,208, issued May 22, 2018, which is a continuation application of U.S. Non-Provisional patent application Ser. No. 14/331,873, filed Jul. 15, 2014, now U.S. Pat. No. 9,557,505, issued Jan. 31, 2017, which claims the benefit of U.S. Provisional Patent Application Ser. No. 61/846,392, filed Jul. 15, 2013 and is a continuation-in-part of PCT Patent Application No. PCT/US2014/030969, filed Mar. 18, 2014, which claims the benefit of U.S. Provisional Patent Application Ser. No. 61/802,989, filed Mar. 18, 2013. The disclosures of all of the above-mentioned patent applications are hereby incorporated by reference in their entireties.

BACKGROUND

The present disclosure relates generally to hybrid optical fiber and electrical communication systems.

Rapid growth of portable high-speed wireless transceiver devices (e.g., smart phones, tablets, laptop computers, etc.) continues in today's market, thereby creating higher demand for untethered contact. Thus, there is growing demand for integrated voice, data and video capable of being transmitted wirelessly at data rates of 10 Gbits/second and faster. To provide the bandwidth needed to support this demand will require the cost effective and efficient deployment of additional fixed location transceivers (i.e., cell sites or nodes) for generating both large and small wireless coverage areas. Fiber optic technology is becoming more prevalent as service providers strive to deliver higher bandwidth communication capabilities to customers/subscribers. The phrase "fiber to the x" (FTTX) generically refers to any network architecture that uses optical fiber in place of copper within a local distribution area. Example FTTX networks include fiber-to-the-node (FTTN) networks, fiber-to-the-curb (FTTC) networks, fiber-to-the-home (FTTH), and more generally, fiber-to-the-wireless (FTTW).

SUMMARY

In accordance with aspects of the present disclosure, examples of a power and optical fiber interface system include a housing having an interior. A cable inlet is configured to receive a hybrid cable having an electrical conductor and an optical fiber. An insulation displacement connector (IDC) is situated in the interior of the housing configured to electrically terminate the conductor, and a cable outlet is configured to receive an output cable that is connectable to the IDC and configured to output signals received via the optical fiber.

In accordance with further aspects of the disclosure, examples of the disclosed system include a power converter, such as a DC-DC converter electrically connected to the IDC. An optical fiber management device, such as an optical splice device, is situated in the interior of the housing and configured to receive the optical fiber. A media board is included in some embodiments that is configured to convert optical signals to electrical signals. In some implementations, the IDC includes a housing with a fiber pass-through groove configured to route optical fibers through the housing of the IDC, and first and second conductor grooves are situated on either side of the fiber pass-through groove to receive first and second conductors.

Another aspect of the present disclosure relates to a powered fiber optic system. The powered fiber optic system includes a first location including a power source and fiber optic network access and a plurality of active devices remotely positioned with respect to the first location. The powered fiber optic system further includes a plurality of hybrid cables routed from the first location toward the active devices. The hybrid cables include optical fibers for transmitting optical signals and electrical conductors for carrying power. The powered fiber optic system further includes interface devices mounted adjacent to the active devices for providing interfaces between the hybrid cables and the active devices. The interface devices include electrical power management circuitry positioned within the closure for providing DC-to-DC voltage conversion within the closure and also include circuit protection circuitry for providing current surge protection.

A further aspect of the present disclosure relates to an interface device for providing an interface between a hybrid cable and an active device. The interface device includes a closure adapted for outside environmental use and a cable anchoring structure for securing a hybrid cable to the closure. The hybrid cable is configured to carry both electrical power and optical signals. The interface device also includes electrical power management circuitry positioned within the closure for providing DC-to-DC voltage conversion within the closure. The electrical power management circuitry is customizable to output one of a plurality of different DC voltage levels such that the DC output level can be matched with a power requirement of the active device. The interface device also includes electrical protection circuitry positioned within the closure and an output configuration for outputting power and communications signals from the interface device to the active device. The output configuration has a format that is customizable and selectable from a plurality of formats that include all of the following formats: a) a power over Ethernet format or a power over Ethernet plus format; and b) a format including one or more optical fibers for the optical signals and separate electrical conductors for power.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a system diagram showing an example distribution of wireless coverage areas deployed using a power and optical fiber interface system in accordance with principles of the present disclosure.

FIG. 2 is a transverse cross-sectional view of a power/optical fiber hybrid cable in accordance with principles of the present disclosure.

FIG. 3 is a perspective view of a portion of the hybrid cable of FIG. 2 with electrically conductive portions of the cable showing separated from a central optical fiber portion of the cable.

3

FIG. 4 is a plan view of the hybrid cable of FIGS. 2 and 3 with the electrically conductive portions of the hybrid cable trimmed relative to the central fiber optic portion of the hybrid cable.

FIG. 5 is a transverse cross-sectional view of another power/optical fiber hybrid cable in accordance with principles of the present disclosure.

FIG. 6 is a block diagram conceptually illustrating aspects of a communication and power distribution system in accordance with principles of the present disclosure.

FIG. 7 is a top view of an interface device in accordance with principles of the present disclosure.

FIG. 8 is a perspective view of the interface device shown in FIG. 7.

FIG. 9 is a partial top view of the interface device shown in FIG. 7, illustrating aspects of an insulation displacement connector (IDC) in an open position.

FIG. 10 is another partial top view of the interface device shown in FIG. 7, illustrating aspects of the IDC in a closed position.

FIG. 11 is a perspective view of the interface device shown in FIG. 7, illustrating an embodiment that includes an optical splice device.

FIG. 12 is a top view of the interface device shown in FIG. 11.

FIG. 13 is a top view of the interface device shown in FIG. 7, illustrating an embodiment that includes a media board.

FIG. 14 is a circuit diagram illustrating an example power conditioning circuit.

FIG. 15 shows a system in accordance with the principles of the present disclosure having a rack mounted power supply.

FIG. 16 shows a hybrid cable system in accordance with the principles of the present disclosure.

DETAILED DESCRIPTION

In the following Detailed Description, reference is made to the accompanying drawings, which form a part hereof, and in which is shown by way of illustration specific embodiments in which the invention may be practiced. In this regard, directional terminology, such as top, bottom, front, back, etc., is used with reference to the orientation of the Figure(s) being described. Because components of embodiments can be positioned in a number of different orientations, the directional terminology is used for purposes of illustration and is in no way limiting. It is to be understood that other embodiments may be utilized and structural or logical changes may be made without departing from the scope of the present invention. The following detailed description, therefore, is not to be taken in a limiting sense.

FIG. 1 shows a system 10 in accordance with the principles of the present disclosure for enhancing the coverage areas provided by cellular technologies (e.g., GSM, CDMA, UMTS, LTE, WiMax, WiFi, etc.). The system 10 includes a base location 11 (i.e., a hub) and a plurality of wireless coverage area defining equipment 12a, 12b, 12c, 12d, 12e and 12f (sometimes collectively referred to as equipment 12 herein) distributed about the base location 11. In certain examples, the base location 11 can include a structure 14 (e.g., a closet, hut, building, housing, enclosure, cabinet, etc.) protecting telecommunications equipment such as racks, fiber optic adapter panels, passive optical splitters, wavelength division multiplexers, fiber splice locations, optical fiber patching and/or fiber interconnect structures and other active and/or passive equipment. In the depicted example, the base location 11 is connected to a central office

4

16 or other remote location by a fiber optic cable such as a multi-fiber optical trunk cable 18 that provides high bandwidth two-way optical communication between the base location 11 and the central office 16 or other remote location. In the depicted example, the base location 11 is connected to the wireless coverage area defining equipment 12a, 12b, 12c, 12d, 12e and 12f by hybrid cables 20. The hybrid cables 20 are each capable of transmitting both power and communications between the base location 11 and the wireless coverage area defining equipment 12a, 12b, 12c, 12d, 12e and 12f.

The wireless coverage area defining equipment 12a, 12b, 12c, 12d, 12e and 12f can each include one or more wireless transceivers 22. The transceivers 22 can include single transceivers 22 or distributed arrays of transceivers 22. As used herein, a “wireless transceiver” is a device or arrangement of devices capable of transmitting and receiving wireless signals. A wireless transceiver typically includes an antenna for enhancing receiving and transmitting the wireless signals. Wireless coverage areas are defined around each of the wireless coverage area defining equipment 12a, 12b, 12c, 12d, 12e and 12f. Wireless coverage areas can also be referred to as cells, cellular coverage areas, wireless coverage zones, or like terms. Examples of and/or alternative terms for wireless transceivers include radio-heads, wireless routers, cell sites, wireless nodes, etc.

In the depicted example of FIG. 1, the base location 11 is shown as a base transceiver station (BTS) located adjacent to a radio tower 24 supporting and elevating a plurality of the wireless coverage area defining equipment 12a. In one example, the equipment 12a can define wireless coverage areas such as a macrocells or microcells (i.e., cells each having a coverage area less than or equal to about 2 kilometers wide). The wireless coverage area defining equipment 12b is shown deployed at a suburban environment (e.g., on a light pole in a residential neighborhood) and the equipment 12c is shown deployed at a roadside area (e.g., on a roadside power pole). The equipment 12c could also be installed at other locations such as tunnels, canyons, coastal areas, etc. In one example, the equipment 12b, 12c can define wireless coverage areas such as microcells or picocells (i.e., cells each having a coverage area equal to or less than about 200 meters wide). The equipment 12d is shown deployed at a campus location (e.g., a university or corporate campus), the equipment 12e is shown deployed at a large public venue location (e.g., a stadium), and the equipment 12f is shown installed at an in-building or near-building environment (e.g., multi-dwelling unit, high rise, school, etc.). In one example, the equipment 12d, 12e, and 12f can define wireless coverage areas such as microcells, picocells, or femtocells (i.e., cells each having a coverage area equal to or less than about 10 meters wide).

The wireless coverage area defining equipment 12 are often located in areas without power outlets conveniently located. As noted above, the hybrid cable 20 provides both power and data to the equipment 12. FIG. 2 is a transverse cross-sectional view taken through an example of one of the hybrid cables 20 of FIG. 1. Hybrid cable 20 includes an outer jacket 200 having a transverse cross-sectional profile that defines a major axis 202 and a minor axis 204. The outer jacket has a height H measured along the minor axis 204 and a width W measured along the major axis 202. The width W is greater than the height H such that the transverse cross-sectional profile of the outer jacket 200 is elongated along the major axis 202.

The outer jacket 200 can include a left portion 206, a right portion 208 and a central portion 210. The left portion 206,

5

the right portion **208** and the central portion **210** can be positioned along the major axis **202** with the central portion **210** being disposed between the left portion **206** and the right portion **208**. The left portion **206** can define a left passage **212**, the right portion **208** can define a right passage **214** and the central portion **210** can define a central passage **216**. The passages **212**, **214** and **216** can have lengths that extend along a central longitudinal axis **218** of the cable **20** for the length of the cable. A left electrical conductor **220** is shown positioned within the left passage **212**, a right electrical conductor **222** is shown positioned within the right passage **214** and at least one optical fiber **224** is shown positioned within the central passage **216**. Certain embodiments include from 1 to 12 fibers **224**, for example. The left electrical conductor **220**, the right electrical conductor **222** and the optical fiber **224** have lengths that extend along the central longitudinal axis **218** of the cable **20**.

Still referring to FIG. 2, the hybrid cable **20** includes a left pre-defined tear location **226** positioned between the central portion **210** and the left portion **206** of the outer jacket **200**, and a right pre-defined tear location **228** positioned between the central portion **210** and the right portion **208** of the outer jacket **200**. The left pre-defined tear location **226** is weakened such that the left portion **206** of the outer jacket **200** can be manually torn from the central portion **210** of the outer jacket **200**. Similarly, the right pre-defined tear location **228** is weakened such that the right portion **208** of the outer jacket **200** can be manually torn from the central portion **210** of the outer jacket **200**. The left pre-defined tear location **226** is configured such that the left portion **206** of the outer jacket **200** fully surrounds the left passage **212** and the central portion **210** of the outer jacket **200** fully surrounds the central passage **216** after the left portion **206** of the outer jacket **200** has been torn from the central portion **210** of the outer jacket **200**. In this way, the left electrical conductor **220** remains fully insulated and the optical fiber **220** remains fully protected after the left portion **206** has been torn from the central portion **210**. The right pre-defined tear location **228** is configured such that the right portion **208** of the outer jacket **200** fully surrounds the right passage **214** and the central portion **210** of the outer jacket **200** fully surrounds the central passage **216** after the right portion **208** of the outer jacket **200** has been torn from the central portion **210** of the outer jacket **200**. In this way, the right electrical conductor **222** remains fully insulated and the optical fiber **224** remains fully protected after the right portion **208** has been torn from the central portion **210**.

FIG. 3 shows the hybrid cable **20** with both the left portion **206** and the right portion **208** torn away from the central portion **210**. In this configuration, both the left electrical conductor **220** and the right electrical conductor **222** are fully insulated by their corresponding left and right portions **206**, **208**. Additionally, the central portion **210** has a rectangular transverse cross-sectional shape that fully surrounds the central passage **216** so as to protect the optical fiber or fibers **224**.

It will be appreciated that the left and right electrical conductors **220**, **222** have a construction suitable for carrying electricity. It will be appreciated that the electrical conductors can have a solid or stranded construction. Example sizes of the electrical conductors include 12 gauge, 16 gauge, or other sizes.

The outer jacket **200** is preferably constructed of a polymeric material. In one example, the hybrid cable **20** and the outer jacket **200** are plenum rated. In certain examples, the outer jacket **200** can be manufactured of a fire-retardant plastic material. In certain examples, the outer jacket **200**

6

can be manufactured of a low smoke zero halogen material. Example materials for the outer jacket include polyvinyl chloride (PVC), fluorinated ethylene polymer (FEP), polyolefin formulations including, for example, polyethylene, and other materials.

The central passage **216** can contain one or more optical fibers **224**. In certain examples, the optical fibers **224** can be coated optical fibers having cores less than 12 microns in diameter, cladding layers less than 240 microns in diameter, and coating layers less than 300 microns in diameter. It will be appreciated that the core and cladding layers typically include a silica based material. In certain examples, the cladding layer can have an index of a refraction that is less than the index of refraction of the core to allow optical signals that are transmitted through the optical fibers to be confined generally to the core. It will be appreciated that in certain examples, multiple cladding layers can be provided. In certain examples, optical fibers can include bend insensitive optical fibers having multiple cladding layers separated by trench layers. In certain examples, protective coatings (e.g., a polymeric material such as acetalate) can form coating layers around the cladding layers. In certain examples, the coating layers can have diameters less than 300 microns, or less than 260 microns, or in the range of 240 to 260 microns. In certain examples, the optical fibers **224** can be unbuffered. In other examples, the optical fibers can include a tight buffer layer, a loose buffer layer, or a semi-tight buffer layer. In certain examples, the buffer layers can have an outer diameter of about 800 to 1,000 microns. The optical fibers can include single mode optical fibers, multi-mode optical fibers, bend insensitive fibers or other fibers. In still other embodiments, the optical fibers **224** can be ribbonized.

As shown in FIG. 4, the left and right portions **206**, **208** can be trimmed relative to the central portion **210** after the left and right portions **206**, **208** have been torn away from the central portion **210**. In this configuration, the central portion **210** extends distally beyond the ends of the left and right portions **206**, **208**. In certain examples, insulation displacement connectors can be used to pierce through the jacket materials of the left and right portions **206**, **208** to electrically connect the left and right electrical connectors **220**, **222** to an electrical power source, ground, active components or other structures. It will be appreciated that the optical fibers **224** can be connected to other fibers with mechanical or fusion splices, or directly terminated with optical connectors. In other examples, connectorized pigtails can be spliced to the ends of the optical fibers **224**.

Referring back to FIG. 2, the outer jacket **200** includes a top side **230** and a bottom side **232** separated by the height **H**. As depicted, the top and bottom sides **230**, **232** are generally parallel to one another. Each of the left and right pre-defined tear locations **226**, **228** includes an upper slit **234** that extends downwardly from the top side **230**, a lower slit **236** that extends upwardly from the bottom side **232** and a non-slitted portion **238** positioned between the upper and lower slits **234**, **236**. In one example embodiment, the upper and lower slits **234**, **236** are partially re-closed slits. In the depicted embodiment, the left and right pre-defined tear locations **226**, **228** also include jacket weakening members **240** that are imbedded in the non-slitted portions **238**. By way of example, the jacket weakening members **240** can include strands, monofilaments, threads, filaments or other members. In certain examples, the jacket weakening members **240** extend along the central longitudinal axis **218** of the cable **20** for the length of the cable **20**. In certain examples, the jacket weakening members **240** are aligned along the

major axis **202**. In certain examples, the upper and lower slits **230**, **236** as well as the jacket weakening member **240** of the left pre-defined tear location **226** are aligned along a left tearing plane PL that is oriented generally perpendicular relative to the major axis **202**. Similarly, the upper and lower slits **234**, **236** as well as the jacket weakening member **240** of the right pre-defined tear location **228** are aligned along a right tearing plane PR that is oriented generally perpendicular with respect to the major axis **202**.

Referring again to FIG. 2, the hybrid cable **20** can include a tensile strength structure **242** that provides tensile enforcement to the hybrid cable **20** so as to prevent tensile loads from being applied to the optical fibers **224**. In certain embodiments, the tensile strength structure **242** can include reinforcing structures such as Aramid yarns or other reinforcing fibers. In still other embodiments, the tensile strength structure **242** can have an oriented polymeric construction. In still other examples, a tensile strength structure **242** can include a reinforcing tape. In certain examples, the reinforcing tape can be bonded to the outer jacket **200** so as to line the central passage **216**. In certain examples, no central buffer tube is provided between the optical fibers **224** and the tensile reinforcing structure **242**. In certain examples, the tensile strength structure **242** can include a reinforcing tape that extends along the length of the hybrid cable **20** and has longitudinal edges/ends **244** that are separated so as to define a gap **244** therein between. In use, the tensile strength member **242** can be anchored to a structure such as a fiber optic connector, housing or other structure so as to limit the transfer of tensile load to the optical fibers **224**. It will be appreciated that the tensile strength structure **242** can be anchored by techniques such as crimping, adhesives, fasteners, bands or other structures.

FIG. 5 shows an alternative hybrid cable **20'** having the same construction as the hybrid cable **20** except two tensile strength structures **242A**, **242B** have been provided within the central passage **216**. Tensile strength members **242A**, **242B** each include a tensile reinforcing tape that is bonded to the central portion **210** of the outer jacket **200**. The tensile strength members **242A**, **242B** can include portions that circumferentially overlap one another within the central passage **216**. In certain examples, by stripping away an end portion of the central portion **210**, the tensile strength structures **242A**, **242B** can be exposed and readily secured to a structure such as a fiber optic connector, a panel, a housing or other structure. In one example, the tensile strength structures **242A**, **242B** can be crimped, adhesively secured or otherwise attached to rods (e.g., epoxy rods reinforced with fibers) that are in turn secured within a ruggedized fiber optic connector such as the fiber optic connector disclosed at U.S. Pat. No. 7,744,288 which is hereby incorporated by reference in its entirety, or the fiber optic connector disclosed at U.S. Pat. No. 7,918,609, which is hereby incorporated by reference in its entirety.

As noted above, the electrical conductors **220**, **222** could be 12 gauge (AWG) or 16 gauge, for example. In certain examples, a 12 gauge conductor **220**, **222** provides up to 1175 meter reach at 15 W, and a 750 meter reach for 25 W devices. The 16 gauge implementations can provide reduced cost for shorter reach applications or lower power devices, for example.

Providing power to remote active devices such as the wireless coverage area defining equipment **12** is often difficult and expensive. Providing required power protection and backup power further complicates powering such remote devices. Optical Network Terminals (ONT's) and Small Cell devices (such as picocells and metrocells) have

“similar” power requirements. For example, 25 W, 12 VDC or 48 VDC devices are common, although variations occur. FIG. 6 conceptually illustrates an example of a communication signal and power distribution system **300** in accordance with aspects of the present disclosure. Among other things, the system **300** provides a simple, “universal” connection of the optical fiber **224** and electrical conductors **220**, **222** of the hybrid cable **20** to the equipment **12**.

The system **300** includes a fiber patch panel **302** that terminates optical fibers carrying signals to be distributed to the desired wireless coverage area defining equipment **12** via the optical fibers **224** of the hybrid cables **20**. A power supply **304** connects to the conductors **220**, **222** of the desired hybrid cable **20**. In some examples, the power supply **304** receives 120/220 VAC and provides 48 VDC nominal. In some embodiments, the fiber patch panel **302** and power supply **304** are rack mounted.

A first end **306** of the hybrid cable **20** is connected to the appropriate optical fibers from the fiber patch panel **302** and to the power supply **304**. A second, distant end **308** of the cable **20** is connected to an interface device **310**. The interface device is connected to the wireless equipment **12**, either directly or through a media converter **312**. Examples of the interface **310** provide simplified termination of the hybrid cable **20**, allowing factory or field installation. In some embodiments, a DC-DC converter provides the desired voltage level for the particular device **12** to which it is connected and compensates for IR loss across variable link lengths.

FIGS. 7-13 illustrate various views of embodiments of the interface device **310**. The interface device **310** includes a body **320** having an exterior **322** and an interior **324**. A cover **326** is connected to the body **320** by a hinge **328** such that the interface device **310** can be opened to expose the interior **324** for access by an operator. A mounting bracket **340** extends from the body **320** for mounting the interface device **310** as desired using screws or bolts, for example. In one example, the interface device **310** defines footprint dimensions of about 55 mm×125 mm×190 mm.

A cable clamp **342** cooperates with the body **320** to fix the hybrid input cable **20** and an output cable **344** to the interface device **310** at a cable inlet **350** and a cable outlet **352**, respectively. As noted above, the hybrid cable **20** includes electrical conductors **220**, **220** for supplying power to the interface device **310**, and ultimately the remote device **12**. In the illustrated examples, the interface device **310** includes an insulation displacement connector (IDC) **360** situated in the interior **324** of the interface device body **320** for connecting the conductors **220**, **220** to the interface device **310**. Generally, an IDC (also sometimes referred to as insulation displacement termination and insulation-piercing connector) is an electrical connector that connects to one or more conductors of an insulated conductor by a connection process that forces a selectively sharpened blade or blades through the insulation to contact the conductor, eliminating the need to strip the insulation before connecting. Further, the connector blades cold weld to the conductors to form a gas-tight connection.

FIGS. 9 and 10 illustrate the IDC **360** in closed and open positions, respectively. As shown in FIG. 3 and discussed in conjunction therewith above, the hybrid cable **20** is configured such that the left portion **206** and the right portion **208** can be torn away from the central portion **210**. In this configuration, both the left electrical conductor **220** and the right electrical conductor **222** are fully insulated by their corresponding left and right portions **206**, **208**. Referring to FIG. 10, the IDC **360** includes a housing **358** with first and

second conductor grooves **362**, **364** positioned on either side of a fiber pass-through groove **366**. Correspondingly, the electrical conductors **220**, **222** of the hybrid cable **20** are situated on either side of the central portion **210** containing the optical fibers **224**.

The conductors **220**, **222** are received by the corresponding conductor grooves **362**, **364**, and insulator clamping ribs **368** are situated to press against the jacket **200** to hold the hybrid cable **20** in place. The IDC **360** includes a cover **370** hingedly connected to the housing **358** that when closed presses IDC terminals **372** against the conductors **220**, **222** and through the left portion **206** and the right portion **208** of the outer jacket **200** to make an electrical connection with the conductors **220**, **222**. The illustrated IDC terminals **372** are angled to provide a gas-tight connection. In the illustrated example, the left and right portions **206**, **208** are trimmed such that the conductors **220**, **222** extend beyond the IDC terminals **372** but remain within the housing **358** of the IDC **360**.

In other embodiments, the IDC is configured in a “pass-through” power arrangement, wherein the terminals **372** pierce the left and right portions **206**, **208** to contact the conductors **220**, **222**, but the left and right portions **206**, **208** are not trimmed so they extend through the IDC **360** to be routed to equipment **12** or another interface device **310**, such as via the cable outlet **352**.

In the illustrated example, a power converter **376**, such as a DC-DC voltage converter, is situated in the interior **324** of the base **320** and electrically connected to the IDC **360** so as to electrically connect the conductors **220**, **222** of the hybrid cable **20** to the power converter **376** via the IDC **360**. Thus, power entering the interface device **310** via the hybrid cable **20** can be conditioned and/or converted to the desired level for the wireless coverage area defining equipment **12** to which the interface device **310** connects. The power converter **376** is connectable to the output cable **344** to route the conditioned/converted power from the interface device **310** to the desired wireless equipment **12**. For instance, conductors of the output cable **344** could connect directly to the power converter **376** using screw terminals **378** thereon. In alternative embodiments, the power converter **376** can be omitted or bypassed if the power received by the interface device **310** is appropriate for the particular end device **12**. Further power connection arrangements are discussed herein below.

The optical fibers **224** from the hybrid cable **20** are received by the centrally positioned fiber pass-through groove **366** to route the optical fibers **224** through the housing **358** of the IDC **360**. The fibers **224** extend from the housing **358** and are routed along the perimeter of the interior **324** of the interface device **310**. In some embodiments, the optical fibers **324** are routed through the interior **324** directly to the cable outlet **352**, along with a separate power output cable. More typically, the fibers **324** would be routed to a fiber management device **380**. In the illustrated example, fiber guides **374** are situated in the corners of the interior **324** for routing the optical fibers **324** in the interface device while maintaining a desired bend radius. In certain implementations, the optical fibers **324** are thus received at the cable inlet **350**, routed through the IDC housing **358** and the interior **324** of the interface device body **320** to the fiber management device **380**.

FIGS. **11** and **12** illustrate an example of the interface device **310** wherein the fiber management device **380** includes an optical splice device for making a mechanical or fusion splice, for example. The illustrated fiber management device **380** thus includes furcation tubes **382** situated on

splice holders **384**. In other implementations, other fiber optic management devices such as fiber optic connectors are provided. A strength member termination **386** is further provided in the embodiment illustrated in FIGS. **11** and **12**.

The optical fibers **224** can thus be spliced, for example, to a fiber optic pig tail and routed to the cable outlet **352**. In some examples, the output cable **244** is also a hybrid cable including optical fibers that are spliced to the fibers **224** using the fiber management device **380**, and conductors that receive power from the power converter **376**.

FIG. **13** illustrates another embodiment where the fiber management device **380** includes a media board **390** that converts optical signals received via the optical fibers **224** to electrical signals. A fiber optic connector **392**, such as an LC duplex input connector, is connected to the media board **390** to terminate the optical fibers routed through the interior **324** of the interface device **310** and receive optical signals therefrom. The media board **390** is electrically connected to the IDC **360**, either directly, or as in the illustrated embodiment, via the power converter **376**. In this manner, the media board is powered by power from the conductors **220**, **222** terminated by the IDC **360**. Additionally, in some embodiments, the media board **390** connects output power and electrical communication signals to a power over Ethernet (POE) connection. In such embodiments, the output cable **344** is a standard RJ-45 data/power cable that connects to a PoE jack **394** on the media board **390**. The RJ-45 cable can then be connected to the desired wireless coverage area defining equipment **12** to provide both communication signals and power thereto.

Some embodiments, for example, include 12 fibers **224** situated in the central passage **216**. Typically, two optical fibers **224** are terminated in a given interface device **310**. Since the two fibers **224** carrying signals for the desired wireless equipment **12** are to be terminated in the interface device **310**, they are cut downstream of the interface device **310**. A slit can be cut in the central portion **216** providing an opening through which the desired fibers **224** can be pulled from the central portion and routed to the fiber management device **380**. The remaining optical fibers **224** remain intact within the central portion **216**, and can be passed through the interface device **310** to another device, for example.

The power converter **276** provides DC/DC conversion, for example, as well as other power management functions such as circuit overload protection, mains cross protection, lightning protection, etc. In one particular embodiment, a 30 W, 12V output DC-DC converter from CUI Inc. of Tualatin, OR (P/N VYC30 W-Q48-S12-T) is used. Other DC-DC converters may be employed based on electrical requirements, packaging, etc. In some implementations, a conditioning circuit is integrated into the interface **310** to minimize voltage ripple. FIG. **14** shows an example of a typical conditioning circuit **400**. In further examples, overvoltage protection, such as a gas-tube, is incorporated between the IDC terminals and DC-DC converter input.

Referring back to FIG. **6**, the fiber patch panel **302** can receive can receive optical signals from a remote location via a fiber optic trunk cable. Optical fibers of the trunk cable **110** can be separated at a fan-out device, or optical power splitters or wavelength division multiplexers can be used to split optical communications signals from the trunk cable to multiple optical fibers. The fibers can be routed to the patch panel **302**, and then to a desired one of the hybrid cables **20**, along with electrical power from the power supply **304**. In one example, the power supply **304** receives 120 volt or 220 volt alternating current. In one example, power supply **302** includes an AC/DC converter that converts the electrical

11

power from alternating current to direct current. The power supply 304 converts the electrical power from the first voltage (e.g., 120v or 220v) to a second voltage that is less than the first voltage. In one example, the second voltage is less than or equal to 60 volts and 100 Watts such that the output voltage complies with NEC Class II requirements.

The hybrid cable 20 can be used to transmit electrical power and optical communication signals from the fiber patch panel 302 and power supply 304 located at a first to the wireless equipment 12 located at a second location. The first end 306 of the hybrid cable 20 can include a first interface for connecting the hybrid cable to electrical power and fiber optic communication at a connector, and the second end 308 of the hybrid cable 20 is received at the cable inlet 350 of the interface device 310. The power converter 376 of the interface device 310 converts electrical power carried by the hybrid cable 20, for example, to a direct current third voltage that is less than the second voltage. In one example, the third voltage corresponds to an electrical voltage requirement of the device 12. In one example, the third voltage is 12V, 24V or 48V.

In some implementations, a converter 312 is associated with the equipment 12 for converting optical signals to electrical signals. In such implementations, the optical fibers and power are provided from the interface device 310 to the converter 312, which provides power and communication signals to the equipment 12. In other implementations, the interface device 310 converts the optical signals to electrical signals using the media board 390, and provides power and electrical communication signals to the equipment 12.

Aspects of the present disclosure relate to powered fiber cable systems capable of simultaneously powering and communicating with wireless coverage area defining equipment (e.g., transceivers, wireless routers, WiFi access points/WiFi hot spots, small cell devices, or like devices). The powered fiber cable system can also be used to power and communicate with other devices such as digital signage, high definition surveillance cameras, and like devices. Moreover, powered fiber cable systems in accordance with the principles of the present disclosure can be incorporated into fiber optic networks (e.g., fiber-to-the-home (FTTH), fiber-to-the-premises (FTTP, fiber-to-the-anything (FTTX)) to provide back-up power or primary power to optical network terminals (ONT) including electronics for providing optical-to-electrical conversion at or near a subscriber location. By providing back-up power using a powered fiber cable system in accordance with the principles of the present disclosure, battery back-ups at the optical network terminals can be eliminated. Powered fiber cable systems in accordance with the principles of the present disclosure are particularly well suited for supporting active devices at outdoor locations where power is not readily available. However, powered fiber cable systems in accordance of the principles of the present disclosure can also be used to support indoor applications such as in local area networks where power and fiber are provided to desk-top locations (e.g., fiber-to-the-desk (FTTD)). Other applications for powered fiber cable systems in accordance with the principles of the present disclosure relate to power-over-Ethernet extensions (PoE or PoE+).

Aspects of the present disclosure relate to systems that provide a "rack to device" vision for both powering and communicating with active devices such as small cell devices, ONT's, WiFi hot spots, digital signage, surveillance cameras or like devices in one cable system. FIG. 15 shows an example powered fiber cable system 400 in accordance with the principles of the present disclosure. The powered

12

fiber cable system 400 includes a rack 402 positioned at a location where power (e.g., a power system/grid that typically provides AC power such as a mains power system) and fiber network are available. Such locations where power and fiber optic network communications are available can be referred to as head ends. In certain examples, the power locations (i.e., head ends) can be co-located at a cell site base station, a base station on a building top, in a telecom closet or data center or anywhere where power and access to a fiber optic network are available. As shown at FIG. 15, a patch panel 404 is mounted on the rack 402. The patch panel 404 is coupled to a fiber optic network. For example, optical fibers optically corresponding to fiber optic distribution or feed cables can be connectorized and plugged into fiber optic adapters supported at the patch panel 404. The rack 402 is also shown supporting a power supply unit 406 that in certain examples provides a DC output of 48 volts or less.

In one example, the power supply can include a power express class II power converter shelf manufactured by General Electric. The power supply can include an AC/DC transformer for transforming alternating current (AC) from a mains power supply into DC power for distribution to remotely located active devices. In certain examples, the power supply 406 can power up to 32 hybrid cables 20 in a modular design with four modules and eight cables per module. In certain examples, the power supply is configured to output relatively low voltage DC current (e.g., less than or equal to 48 volts DC). In certain examples, the power source is National Electric Code (NEC) class 2 (as specified by Article 725) and Safety Extra Low Voltage (SELV) compliant. In certain examples, the voltage between any two conductors should not exceed 60 volts DC under normal operating conditions. In certain examples, the power supply is limited to 100 VA. Such low voltage circuits are advantageous because electricians are not required to install such systems, such systems are inherently safe because of the low voltage limits, and such systems can be installed in a conduit-free manner. In certain examples, the power supply can also include circuit protection electronics such as gas discharge tubes, metal oxide varistor components and transient voltage suppression structures/diodes.

As shown at FIG. 15, the patch panel 404 and the power supply 406 are both rack mounted. Optical communication lines from the patch panel 404 and power lines from the power source 406 are coupled to hybrid cables 20 routed to universal interface devices 310 that support active devices such as a picocell 408, a metrocell 410, a femtocell 412 and an ONT 414. The ONT 414 is shown connected to the corresponding interface device 310 by a power line 415 and a separate fiber line 417. The picocell 408, metrocell 410 and femtocell 412 are coupled to their corresponding interface devices 310 by power lines 419 and two fiber lines 421, 423. In other examples, the fiber lines 421, 423 can be replaced with twisted pair conductors for carrying electrical signals in cases where optical to electrical signal conversion occurs at the interface device 310.

Further aspects of the present disclosure relate to a remote interface device (e.g., interface device 310 that is remote from the power supply) for providing an interface between a hybrid cable and a remote active device, the interface device including a closure that houses circuitry for providing electrical power management and including circuit protection electronics. It will be appreciated that the circuitry within the closure is adapted for providing an effective interface between a hybrid cable (e.g., hybrid cable 20) and a remote active device. In certain examples, the closure is designed for outdoor environmental use and includes an

13

environmentally sealed construction. In certain examples, the electrical power management circuitry eliminates the need for line power system design. For example, the electrical power management circuitry can include a DC-to-DC converter suitable for converting power carried by one of the hybrid cables **20** to a voltage and power level compatible with an active device intended to be powered with power from the hybrid cable **20**. In certain examples, the DC-to-DC converter can increase the voltage of the power carried by the hybrid cable **20** to a level compatible with the active device powered by the hybrid cable. In certain examples, the increase in voltage provided by the DC-to-DC converter compensates for voltage loss that may occur over the length of the hybrid cable. In certain examples, the DC-to-DC converter raises the voltage level to 12 volts, 24 volts or 48 volts. In certain other examples, the DC-to-DC converter decreases the voltage level to a level compatible with the active device intended to be powered by the hybrid cable. In certain examples, the power is converted so as to become compatible with a 25 watt device, a 30 watt device, or a 45 watt device. In certain examples, the closure also houses an optical-to-electrical converter that converts optical signals from the hybrid cable to electrical signals that are transmitted to the active device. In certain examples, the electrical signals and the power can be transmitted from the interface device to the active device by a twisted pair Ethernet cable so as to provide power-over-Ethernet or power-over-Ethernet-plus connectivity.

As indicated above, the closure of the interface device can enclose circuit protection electronics. For example, the circuit protection electronics can include primary electrical protection that may include a gas discharge tube rated to at least 40 kAmp surge/overvoltage protection. Such structure can provide protection with respect to lightning strikes and line cross-overs. The electrical protection can also include secondary electrical protection that may be rated to 4.5 kAmp and that may include metal oxide varistor components that couple to ground in response to voltage surges. The electrical protection may also include tertiary protection that prevents voltage from rising above a predetermined level (e.g., 80 volts, or 100 volts). In certain examples, the tertiary protection can include a transient voltage suppression diode. In certain examples, fast acting fuses can be used.

Cables in accordance with the principles of the present disclosure can provide power over relatively long distances. For example, using 12 gauge conductors in the hybrid cable and using conversion circuitry in the interface device that converts the optical signals and power to a PoE format, the system can provide 10 Watts of power over a length of 3,000 meters, 15 Watts of power over 2,400 meters, 20 Watts of power over 1,900 meters and 25 Watts of power over 1,600 meters. If power is provided in a non-power over Ethernet format (e.g., via an M8 plug or other power lines separate from the communications lines), 30 watt power can be provided up to 1,600 meters and 45 watt power can be provided up to 1,000 meters. A system that utilizes 16 gauge conductors and outputs power in a power over Ethernet format can provide 10 watts of power at 1,200 meters, 15 watts of power at 960 meters, 20 watts of power at 760 meters, and 25 watts of power at 640 meters. By not using a power over Ethernet format and instead keeping the power separate from the communications via a separate power line, the 16 gauge wire can provide 30 watts of power at 640 meters and 45 watts of power at 400 meters.

Aspects of the present disclosure relate to interface closures that can be readily customized to meet customer

14

requirements. In certain examples, the closures can be environmentally sealed and can include clamps for clamping hybrid cables such as the hybrid cable **20**. The closures can also include power management circuitry such as power converters (e.g., DC-to-DC power converters). The power converters can be customized to comply with the power requirements of the remote device intended to be powered by the customer. In certain examples, the power conversion circuitry can be modular and modules providing different levels of conversion can be selected and plugged into the circuit board of the closure to satisfy the customer requirement. For example, power converters capable of outputting 12, 24 or 48 volts can be used. It will be appreciated that the format of the power output from the interface closure can also be customized to meet customer needs. For example, the interface closure can be configured to output power and communications over a variety of formats such as: (a) power-over-Ethernet; (b) power-over-Ethernet-Plus; (c) separate power (e.g., via a cable terminated with an M8 plug or other configuration) and Ethernet lines (e.g., terminated with RJ45 connectors or other connectors); (d) separate fiber lines for communications and power lines for power (e.g., terminated with M8 connectors or other power connectors); (e) a hybrid cable having optical fibers for optical signals and electrical conductors for power that can be terminated with a hybrid connector or can have separate fiber and power pigtails; or (f) a cable having twisted pair conductors for carrying communication signals and separate electrical conductors for power that can be terminated by separate RJ-style connectors for communication signals and an M8 plug for power or other connector arrangements. In the case where separate fiber lines are used, the fiber lines can be terminated with different styles of fiber optic connectors such as LC connectors, SC connectors, or other fiber optic connectors. In certain examples, the fiber optic connectors can be ruggedized and can include environmental sealing as well as twists-to-lock fastening elements such as threaded fasteners or bayonet-style fasteners. In the case of Ethernet cable, standard RJ-45 connectors or ruggedized RJ-45 connectors can be used. For pigtails carrying only power, stranded or solid conductors can be used. Additionally, the power pigtails can be terminated with power connectors such as M8 connectors.

FIG. **16** shows a cable system **100** that can be used to transmit power and communications from a first location **102** to an active device **104** at a second location **106**. The second location **106** is remote from the first location **102**. In certain example, the first location **102** can be a base location and the active device **104** can include wireless coverage area defining equipment. Examples of wireless coverage area defining equipment and locations where such equipment may be installed are described above. Examples of other types of active devices include cameras such as high definition video cameras.

The first location **102** receives optical signals from a remote location **108** via a fiber optic trunk cable **110**. Optical fibers of the trunk cable **110** can be separated at a fan-out device **111** at the first location. Alternatively, optical power splitters or wavelength division multi-plexers can be used to split optical communications signals from the trunk cable **110** to multiple optical fibers. The fibers can be routed to a patch panel **112** having fiber optic adapters **114** (i.e., structures for optically and mechanically interconnecting two fiber optic connectors **115**). The first location **102** can also include a combined power/communication panel **116** having fiber optic adapters **117** paired with power adapters **118** (i.e.,

15

ports). Connectorized fiber optic patch cords **120** can be routed from the fiber optic adapters **114** to the fiber optic adapters **117**.

The first location **102** can receive electrical power from a main power line **122**. In one example the main power line **122** can be part of a mains power system that provides 100-240 nominal volt alternating current (example frequencies include 50 and 60 Hertz). The first location **102** can include a converter **124** for converting the electrical power from the first voltage (e.g., 100v, 120v, 220v, 230v, 240v etc. nominal voltage) to a second voltage that is less than the first voltage. In one example, the second voltage is less than or equal to 60 volts and less than or equal to 100 Watts such that the output voltage complies with NEC Class II requirements. In one example, the converter **124** is an AC/DC converter that converts the electrical power from alternating current to direct current. Connectorized power cords **126** can be used to route electrical power having the second voltage from the converter **124** to the power adapters **118**. In certain examples, the combined power/communications panel **116** can include at least 18, 24, 30 or 32 fiber optic adapters paired with corresponding power adapters **118**. In certain examples, the converter **124** is large enough to provide NEC Class II compliant power through separate hybrid cables to at least 18, 24, 30 or 32 active devices. Of course, converter having smaller capacities could be used as well. Additionally, the converter **124** can be part of a voltage conversion package including overvoltage protection that provides protection/grounding in the event of lightning strikes and main crosses.

A hybrid cable **20** can be used to transmit electrical power and optical communication signals between the first and second locations **102**, **106**. The hybrid cable **20** can include an outer jacket **150** containing at least one optical fiber **152** for carrying the optical communication signals and electrical conductors **154** (e.g., wires such as ground and power wires) for transmitting the electrical power having the second voltage. The hybrid cable **20** can include a first end **156** and a second end **158**. The first end **156** can include a first interface for connecting the hybrid cable to electrical power and fiber optic communication at the first location **102**. In one example, the first interface can include a power connector **160** (e.g., a plug) that connects the electrical conductors **154** to one of the connectorized power cords **126** at the power/communications panel **116**. The power connector **160** can be plugged into the adapter **118** and can be provided at a free end of a cord that extends outwardly from the outer jacket **150** at the first end of the hybrid cable **20**. The cord can contain the electrical conductors **154**. The first interface can also include a fiber optic connector **162** (e.g., an SC connector, LC connector, ST-style connector or other type of connector) that connects the optical fiber **152** to one of the patch cords **120**. The fiber optic connector **162** can plug into one of the fiber optic adapters **117** and can be mounted at the free end of a cord that contains the optical fiber **152** and extends outwardly from the outer jacket **150** at the first end of the hybrid cable **20**.

The second end **158** of the hybrid cable **20** can include a second interface for connecting the hybrid cable **20** to the active device **104** such that electrical power is provided to the active device **104** and such that fiber optic communication signals can be transmitted between the first and second locations **102**, **106**. The second interface includes an interface structure **164** including a power connection location **166** and a communication connection location **168**. In one example, the interface structure **164** includes a power converter **170** for converting electrical power carried by the

16

hybrid cable **20** to a direct current third voltage that is less than the second voltage. In one example, the third voltage corresponds to an electrical voltage requirement of the active device **104**. In one example, the power converter **170** is a DC/DC converter. In one example, the third voltage is 12V, 24V or 48V. In examples where AC current is transmitted by the hybrid cable **20**, the power converter **124** can be an AC/AC converter and the power converter **170** can be an AC/DC converter. In certain examples, the interface structure **164** can include an optical-to-electrical converter for converting the communications signals carried by the optical fiber **152** from an optical form to an electrical form. In other examples, optical-to-electrical conversion can be performed by the active device **104** or can take place between the active device **104** and the interface structure **164**.

In one example, the interface structure **164** includes a converter interface that allows power converters **170** with different conversion ratios to interface and be compatible with the interface structure **164**. The conversion ratio of the particular power converter **170** used can be selected based on factors such as the voltage requirement of the active device **104** and the length of the hybrid cable **20**. The power converters **170** can have a modular configuration can be installed within the interface structure **168** in the field or in the factory. In one example, the power converters **170** can have a "plug-and-play" interface with the interface structure. The modular configuration also allows the power converter **170** to be easily replaced with another power converter **170**, if necessary. In certain examples, the interface structure **164** can include overvoltage protection and grounding arrangements such as fuses, metal oxide varistors, gas tubes or combinations thereof.

In one example, the electrical power having the third voltage can be output to the active device **104** through the power connection location **166**. The power connection location **166** can include a power connector, a power port, a power cord or like structures for facilitating connecting power to the active device **104**. In one example, the power connection location **166** can have a modular configuration that allows interface connectors having different form factors to be used.

In one example, the communications signals can be transferred between the hybrid cable **20** and the active device through the communication connection location **168**. The communication connection location **168** can include a connector, a port, a cord or like structures for facilitating connecting to the active device **104**. In one example, the communication connection location **168** can have a modular configuration that allows interface connectors having different form factors to be used. In the case where the optical to electrical converter is provided within the interface structure **164**, the connection location can include electrical communication type connectors (e.g., plugs or jacks) such as RJ style connectors. In the case where the optical to electrical converter is provided at the active device **104**, the communication connection location **168** can include fiber optic connectors and or fiber optic adapters (e.g., SC connectors/adapters; LC connectors/adapters, etc.). In certain examples, ruggedized, environmentally sealed connectors/adapters can be used (e.g., see U.S. Pat. Nos. 8,556,520; 7,264,402; 7,090,407; and 7,744,286 which are hereby incorporated by reference in their entireties. It will be appreciated that when the active devices include wireless transceivers, the active devices can receive wireless signals from the coverage area and such signals can be carried from the active devices to the base station **11** via the hybrid cables. Also, the active devices

17

can covert signals received from the hybrid cables into wireless signals that are broadcasted/transmitted over the coverage area.

In one example, the second voltage is less than the first voltage and greater than the third voltage. The third voltage is the voltage required by the active device at the second location. In one example, the second voltage is sufficiently larger than the third voltage to account for inherent voltage losses that occur along the length of the hybrid cable.

Various modifications and alterations of this disclosure may become apparent to those skilled in the art without departing from the scope and spirit of this disclosure, and it should be understood that the scope of this disclosure is not to be unduly limited to the illustrative examples set forth herein.

What is claimed is:

1. A method for providing electrical power and communication signals to an outdoor located active device, the method comprising:

converting the electrical power from an AC voltage to a DC voltage at a first location;

transmitting the electrical power having the DC voltage through a hybrid cable from the first location to an interface device at a second location, the interface device being adapted for outside environmental use and having an environmentally sealed construction;

transmitting the communication signals in an optical form through the hybrid cable from the first location to the interface device at the second location;

converting the electrical power at the interface device to an active device compatible DC voltage;

converting the communication signals at the interface device from the optical form to an electrical form; and transmitting the electrical power having the active device compatible DC voltage and the communication signals in the electrical form from the conversion device to the outdoor located active device via an Ethernet cable having twisted pair conductors.

2. The method of claim 1, wherein the outdoor located active device comprises at least one of a wireless transmitter device and a camera device.

3. The method of claim 1, wherein the conversion device includes a housing having a cover that can be opened and closed, wherein an interior of the housing is accessible by opening the cover, and wherein the cover is required to be opened to connect the Ethernet cable to optical-to-electrical conversion circuitry and power management circuitry within the interior of the housing.

4. The method of claim 1, wherein the hybrid cable is routed outdoors.

5. The method of claim 1, wherein the hybrid cable is plenum rated.

6. A powered fiber system comprising:

a hybrid cable having an electrical conductor and an optical fiber;

a first interface device including voltage conversion circuitry for converting electrical power from a AC volt-

18

age to a first DC voltage, the first interface device having a power interface for sending electrical power having the first DC voltage through the electrical conductor of the hybrid cable and an optical interface for sending optical signals through the optical fiber of the hybrid cable;

an Ethernet cable including first and second wires arranged in a twisted pair configuration;

a second interface device that is adapted for outside environmental use and that has an environmentally sealed construction, the second interface device including a housing defining an interior, the housing including a first port for allowing the hybrid cable to be routed into the interior of the housing and a second port for allowing the Ethernet cable to be routed into the interior of the housing, the second interface device including electrical power management circuitry positioned within the interior of the housing, the electrical power management circuitry being configured to be coupled between the electrical conductor of the hybrid cable and the twisted pair wires of the Ethernet cable, the electrical power management circuitry having a DC-to-DC voltage converter for converting the electrical power received from the hybrid cable to a voltage suitable for transmission over the first and second wires of the Ethernet cable, the second interface device also including optical-to-electrical conversion circuitry positioned within the interior of the housing for connecting the optical fiber of the hybrid cable to the first and second wires of the Ethernet cable, the optical-to-electrical conversion circuitry being configured to convert the optical signals from the optical fiber into electrical signals that are transmitted over the first and second wires of the Ethernet cable.

7. The powered fiber system of claim 6, wherein the housing has a cover that can be opened and closed, wherein the interior of the housing is accessible by opening the cover, and wherein the cover is required to be opened to connect the Ethernet cable to the optical-to-electrical conversion circuitry and the electrical power management circuitry within the interior of the housing.

8. The powered fiber system of claim 6, wherein the hybrid cable is plenum rated.

9. The powered fiber optic system of claim 6, further comprising circuit protection circuitry in the interior of the housing for providing current surge protection.

10. The powered fiber optic system of claim 9, wherein the circuit protection circuitry provides primary, secondary and tertiary protection.

11. The powered fiber optic system of claim 9, wherein the circuit protection circuitry includes a transient voltage suppression diode.

12. The powered fiber optic system of claim 6, further comprising cable clamps configured to fix the hybrid cable and the Ethernet cable to the housing respectively at the first and second cable ports.

* * * * *